

SEL-387 Commissioning Test Example 1

Background:

A technician calls while performing commissioning tests. The substation phone connects you to the SEL-2020. An SEL-387 (Port 4) is connected to the high-side cts of a 69-12 kV power transformer via Winding One, and to two load side feeders via Windings Two and Three. The following information was downloaded with one feeder (Winding Two) closed and carrying load and the other feeder (Winding Three) open. An SEL-351 (Port 5) is used for high-side phase (A,B,C currents) and neutral (N current) back-up.

Answer the question, "Is the SEL-387 ready to go into service?" using the following screen captures and the SEL-387 Commissioning Worksheet.

The following settings were found using the SHOWSET command on the SEL-387.

=>SHO
Group 1

```

RID      =SEL387 98229032
TID      =PAULS VALLEY TRANSF.2
E87W1    = Y      E87W2    = Y      E87W3    = Y      E87W4    = N
EOC1     = Y      EOC2     = Y      EOC3     = Y      EOC4     = N
EOCC     = N      ESLS1    = Y      ESLS2     = N      ESLS3     = N

W1CT     = Y      W2CT     = Y      W3CT     = Y      W4CT     = Y
CTR1     = 120    CTR2     = 240    CTR3     = 240    CTR4     = 1
MVA      = OFF    ICOM     = Y
W1CTC    = 0      W2CTC    = 1      W3CTC     = 1

TAP1     = 2.01   TAP2     = 5.55   TAP3     = 5.55
O87P     = 0.3    SLP1     = 40     SLP2     = OFF
U87P     = 8.0    PCT2     = 15     PCT5     = 35
TH5P     = OFF    INBL     = N
  
```

The following is a METER command on the SEL-351 transformer back-up (to get the total transformer load).

=>MET

```

SEL-351 98229034          Date: 02/22/99   Time: 16:12:10.291
PAULS VALLEY BANK 2 BACKUP

I MAG (A)      A      B      C      N      G
                34.529  38.369  34.708  60.291  0.436
I ANG (DEG)    57.38  -65.29  170.38  83.12   3.45

V MAG (KV)     A      B      C      S
                41.111  41.191  41.007  0.002
V ANG (DEG)    0.00  -119.80  119.52  -64.91

MW             A      B      C      3P
                0.765  0.917  0.898  2.581
MYAR           -1.196  -1.287  -1.104  -3.586
PF             0.539  0.581  0.631  0.584
                LEAD   LEAD   LEAD   LEAD

MAG            I1      I2      I3      V1      V2      3V0
                35.825  7.503  0.436  41.102  0.163  0.443
ANG (DEG)      54.17  179.38  3.45  -0.09  147.73  -7.70

FREQ (Hz)      60.01                VDC (V)      133.7
  
```

Use the 3P MW and MVAR readings on the SEL-351 back-up relay to fill in the Metered Load section of the SEL-387 Commissioning Test Worksheet (Section 10 of the SEL-387 I.M.). Use these numbers to calculate expected relay load. We assume that Winding Two power must equal Winding One (power through the transformer is constant, minus losses). (we could have done a meter command on the Feeder on Winding Two to read the actual power).

Also, note the neutral current? 60 Amps. Can you provide an answer as to why the neutral current does not match the high-side ground current calculated by $3I_0 = I_a + I_b + I_c$? (Delta high-side winding prevents ground current from being seen at the high-side CTs) Why might the neutral current be so high? (load unbalance on the feeder) Does this neutral current magnitude and angle make sense, and how might we determine this? (Calculate the unbalance from the Winding Two currents with $3I_0 = I_a + I_b + I_c$ or measure the neutral current on the feeder relay)

The following was retrieved from the SEL-387 using the MET DIF and MET SEC commands. Use this data to fill in page two of the commissioning worksheet.

=>MET DIF

SEL387 98229032
PAULS VALLEY TRANSF.2

Date: 02/22/99 Time: 16:16:19.530

	Operate Currents			Restraint Currents		
	IOP1	IOP2	IOP3	IRT1	IRT2	IRT3
I (Mult. of Tap)	0.01	0.00	0.01	0.15	0.16	0.14

	Second Harmonic Currents			Fifth Harmonic Currents		
	I1F2	I2F2	I3F2	I1F5	I2F5	I3F5
I (Mult. of Tap)	0.00	0.00	0.00	0.00	0.00	0.00

=>MET SEC

SEL387 98229032
PAULS VALLEY TRANSF.2

Date: 02/22/99 Time: 16:15:00.542

	Phase Currents			Sequence Currents		
	I AW1	I BW1	I CW1	3I1W1	3I2W1	IRW1
I (A, sec)	0.29	0.31	0.29	0.89	0.05	0.01
Angle (deg)	0.00	-124.15	112.61	-3.87	116.34	81.49

	I AW2	I BW2	I CW2	3I1W2	3I2W2	IRW2
I (A, sec)	0.82	0.78	0.89	2.47	0.17	0.23
Angle (deg)	152.66	32.65	-99.67	148.26	-33.85	-160.47

	I AW3	I BW3	I CW3	3I1W3	3I2W3	IRW3
I (A, sec)	0.00	0.00	0.00	0.00	0.00	0.00
Angle (deg)	-35.07	-35.07	-35.07	-35.07	-35.07	-35.07

	I AW4	I BW4	I CW4	3I1W4	3I2W4	IRW4
I (A, sec)	0.00	0.00	0.00	0.00	0.00	0.00
Angle (deg)	-35.07	144.93	-35.07	-95.07	24.93	144.93

Is the SEL-387 ready to go into service?

COMMISSIONING TEST WORKSHEET

SEL-387 Relay

Page 1 of 2

SYSTEM INFORMATION

System Settings

RID (Relay identification) = _____

TID (Terminal identification) = _____

MVA (Maximum transformer rating) = _____

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Current transformer connection:	W1CT = _____	W2CT = _____	W3CT = _____	W4CT = _____
Current transformer ratio:	CTR1 = _____	CTR2 = _____	CTR3 = _____	CTR4 = _____
Connection compensation:	W1CTC = _____	W2CTC = _____	W3CTC = _____	W4CTC = _____
Nominal line-to-line voltage (kV):	VWDG1 = _____	VWDG2 = _____	VWDG3 = _____	VWDG4 = _____
Tap calculation:	TAP1 = _____	TAP2 = _____	TAP3 = _____	TAP4 = _____

Differential Settings

O87P = _____ SLP1 = _____ SLP2 = _____ IRS1 = _____ U87P = _____

Metered Load (Data taken from substation panel meters, not the SEL-387 Relay)

± Readings from meters	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Megawatts:	MW1 = _____	MW2 = _____	MW3 = _____	MW4 = _____
Megavars:	MVAR1 = _____	MVAR2 = _____	MVAR3 = _____	MVAR4 = _____
MVA calculation:				
$MVA_n = \sqrt{MW_n^2 + MVAR_n^2}$	MVA1 = _____	MVA2 = _____	MVA3 = _____	MVA4 = _____

Calculated Relay Load

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Primary Amperes calculation:				
$I_{pri} = \frac{MVA_n \cdot 1000}{\sqrt{3} \cdot VWDG_n}$	I1pri = _____	I2pri = _____	I3pri = _____	I4pri = _____
Secondary Amperes calculation:				
$W_nCT = Y, \quad I_{nsec} = \frac{I_{pri}}{CTR_n}$	I1sec = _____	I2sec = _____	I3sec = _____	I4sec = _____
$W_nCT = D, \quad I_{nsec} = \frac{I_{pri} \cdot \sqrt{3}}{CTR_n}$				

COMMISSIONING TEST WORKSHEET

SEL-387 Relay

Page 2 of 2

CONNECTION CHECK

Differential Connection (issue **MET DIF<ENTER>** to serial port or front panel)

Note: System load conditions should be higher than 0.1 A secondary. 0.5 A secondary is recommended for the best results.

Operate Current: IOP1 = _____ IOP2 = _____ IOP3 = _____

Restraint Current: IRT1 = _____ IRT2 = _____ IRT3 = _____

Mismatch Calculation:


$MMn = IOPn / IRTn$ MM1 = _____ MM2 = _____ MM3 = _____

Check individual current magnitudes, phase angles, and operate and restraint currents in an event report if mismatch is not less than 0.10.

MAGNITUDE, ANGLE, AND PHASE ROTATION CHECK

(issue **MET SEC<ENTER>** to the serial port or front panel)

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
A-Phase Secondary Amperes:	IAW1 = _____	IAW2 = _____	IAW3 = _____	IAW4 = _____
A-Phase Angle:	_____	_____	_____	_____
B-Phase Secondary Amperes:	IBW1 = _____	IBW2 = _____	IBW3 = _____	IBW4 = _____
B-Phase Angle:	_____	_____	_____	_____
C-Phase Secondary Amperes:	ICW1 = _____	ICW2 = _____	ICW3 = _____	ICW4 = _____
C-Phase Angle:	_____	_____	_____	_____



1. Calculated relay amperes match MET SEC amperes?
2. Phase rotation is as expected for each winding?
3. Do angular relationships among windings correspond to expected results? (Remember that secondary current values for load current flowing out of a winding will be 180° out of phase with the reference phase position for that winding. The reason is that ct polarity marks normally face away from the transformer on all windings.)

SEL-387 Commissioning Test Example 2

Background:

A technician calls while performing commissioning tests. The substation phone connects you to the SEL-2020. An SEL-387 is connected to the high-side cts of a 69-12 kV power transformer via Winding One, and to two load side feeders via Windings Two and Three. The following information was downloaded with both low-side feeders in service. An SEL-351 is used for high-side phase (A,B,C currents) and neutral (N current) back-up.

Answer the question, "Is the SEL-387 ready to go into service?" using the following screen captures and the SEL-387 Commissioning Worksheet.

The following settings were found using the SHOWSET command on the SEL-387.

=>SHO
Group 1

```
RID      =SEL387 98229031
TID      =PAULS VALLEY TRANSF. 1
E87W1    = Y      E87W2    = Y      E87W3    = Y      E87W4    = N
EOC1     = Y      EOC2     = Y      EOC3     = Y      EOC4     = N
EOCC     = N      ESLS1    = Y      ESLS2    = N      ESLS3    = N

W1CT     = Y      W2CT     = Y      W3CT     = Y      W4CT     = Y
CTR1     = 120    CTR2     = 240    CTR3     = 240    CTR4     = 1
MVA      = OFF    ICOM     = Y
W1CTC    = 0      W2CTC    = 1      W3CTC    = 1

TAP1     = 2.01   TAP2     = 5.55   TAP3     = 5.55
O87P     = 0.3    SLP1     = 40     SLP2     = OFF
U87P     = 8.0    PCT2     = 15     PCT5     = 35
TH5P     = OFF    IHBL     = N
```

The following is a METER command on the SEL-351 transformer back-up (to get the total transformer load).

=>METER

```
SEL351                               Date: 03/10/99   Time: 16:01:50.981
PAULS VALLEY BANK 1 BU

      A      B      C      N      G
I MAG (A)  43.293  39.188  40.577  44.004  0.333
I ANG (DEG)  9.32  -111.80  133.36  -160.36  22.27

      A      B      C      S
V MAG (KV)  41.278  41.093  41.498  0.002
V ANG (DEG)  0.00  -120.00  120.04  -63.36

      A      B      C      3P
MW          1.763  1.594  1.639  4.996
MVAR        -0.289 -0.230 -0.388 -0.907
PF           0.987  0.990  0.973  0.984
            LEAD   LEAD   LEAD   LEAD

      I1      3I2      3I0      V1      V2      3V0
MAG          40.989   6.953   0.333  41.290   0.123   0.338
ANG (DEG)    10.29   -8.87   22.27   0.02  -88.50   97.61

FREQ (Hz)    60.01                VDC (V)    134.0
```

The following was retrieved from the SEL-387 using the MET DIF and MET SEC commands.
Use this data to fill in page two of the commissioning worksheet.

=>MET DIF

SEL387 98229031
PAULS VALLEY TRANSF. 1

Date: 03/10/99 Time: 16:10:25.851

	Operate Currents			Restraint Currents		
	IOP1	IOP2	IOP3	IRT1	IRT2	IRT3
I (Mult. of Tap)	0.01	0.00	0.01	0.19	0.18	0.19
	Second Harmonic Currents			Fifth Harmonic Currents		
	I1F2	I2F2	I3F2	I1F5	I2F5	I3F5
I (Mult. of Tap)	0.00	0.00	0.00	0.00	0.00	0.00

=>MET SEC

SEL387 98229031
PAULS VALLEY TRANSF. 1

Date: 03/10/99 Time: 16:10:16.927

	Phase Currents			Sequence Currents		
	IAW1	IBW1	ICW1	3I1W1	3I2W1	IRW1
Wdg1						
I (A, sec)	0.37	0.33	0.35	1.05	0.04	0.02
Angle (deg)	0.00	-121.21	121.68	0.17	-16.28	35.88
Wdg2						
I (A, sec)	0.29	0.29	0.37	0.94	0.14	0.19
Angle (deg)	-150.66	72.14	-17.73	-150.88	178.37	7.01
Wdg3						
I (A, sec)	0.82	0.83	0.82	2.47	0.03	0.01
Angle (deg)	130.55	11.22	-109.91	130.62	-57.32	62.45
Wdg4						
I (A, sec)	0.00	0.00	0.00	0.01	0.00	0.01
Angle (deg)	-72.55	107.45	17.45	-117.55	62.45	62.45

Is the SEL-387 ready to go into service?

COMMISSIONING TEST WORKSHEET

SEL-387 Relay

Page 1 of 2

SYSTEM INFORMATION

System Settings

RID (Relay identification) = _____

TID (Terminal identification) = _____

MVA (Maximum transformer rating) = _____

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Current transformer connection:	W1CT = _____	W2CT = _____	W3CT = _____	W4CT = _____
Current transformer ratio:	CTR1 = _____	CTR2 = _____	CTR3 = _____	CTR4 = _____
Connection compensation:	W1CTC = _____	W2CTC = _____	W3CTC = _____	W4CTC = _____
Nominal line-to-line voltage (kV):	VWDG1 = _____	VWDG2 = _____	VWDG3 = _____	VWDG4 = _____
Tap calculation:	TAP1 = _____	TAP2 = _____	TAP3 = _____	TAP4 = _____

Differential Settings

O87P = _____ SLP1 = _____ SLP2 = _____ IRS1 = _____ U87P = _____

Metered Load (Data taken from substation panel meters, not the SEL-387 Relay)

± Readings from meters	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Megawatts:	MW1 = _____	MW2 = _____	MW3 = _____	MW4 = _____
Megavars:	MVAR1 = _____	MVAR2 = _____	MVAR3 = _____	MVAR4 = _____
MVA calculation:				
$MVA_n = \sqrt{MW_n^2 + MVAR_n^2}$	MVA1 = _____	MVA2 = _____	MVA3 = _____	MVA4 = _____

Calculated Relay Load

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Primary Amperes calculation:				
$I_{npri} = \frac{MVA_n \cdot 1000}{\sqrt{3} \cdot VWDG_n}$	I1pri = _____	I2pri = _____	I3pri = _____	I4pri = _____
Secondary Amperes calculation:				
$W_nCT = Y, \quad I_{nsec} = \frac{I_{npri}}{CTR_n}$	I1sec = _____	I2sec = _____	I3sec = _____	I4sec = _____
$W_nCT = D, \quad I_{nsec} = \frac{I_{npri} \cdot \sqrt{3}}{CTR_n}$				

COMMISSIONING TEST WORKSHEET

SEL-387 Relay

Page 2 of 2

CONNECTION CHECK

Differential Connection (issue **MET DIF** <ENTER> to serial port or front panel)

Note: System load conditions should be higher than 0.1 A secondary. 0.5 A secondary is recommended for the best results.

Operate Current: IOP1 = _____ IOP2 = _____ IOP3 = _____

Restraint Current: IRT1 = _____ IRT2 = _____ IRT3 = _____

Mismatch Calculation:


$MM_n = IOP_n / IRT_n$ MM1 = _____ MM2 = _____ MM3 = _____

Check individual current magnitudes, phase angles, and operate and restraint currents in an event report if mismatch is not less than 0.10.

MAGNITUDE, ANGLE, AND PHASE ROTATION CHECK

(issue **MET SEC** <ENTER> to the serial port or front panel)

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
A-Phase Secondary Amperes:	IAW1 = _____	IAW2 = _____	IAW3 = _____	IAW4 = _____
A-Phase Angle:	_____	_____	_____	_____
B-Phase Secondary Amperes:	IBW1 = _____	IBW2 = _____	IBW3 = _____	IBW4 = _____
B-Phase Angle:	_____	_____	_____	_____
C-Phase Secondary Amperes:	ICW1 = _____	ICW2 = _____	ICW3 = _____	ICW4 = _____
C-Phase Angle:	_____	_____	_____	_____



1. Calculated relay amperes match MET SEC amperes?
2. Phase rotation is as expected for each winding?
3. Do angular relationships among windings correspond to expected results? (Remember that secondary current values for load current flowing out of a winding will be 180° out of phase with the reference phase position for that winding. The reason is that ct polarity marks normally face away from the transformer on all windings.)

COMMISSIONING TEST WORKSHEET

SEL-387 Relay

Page 1 of 2

SYSTEM INFORMATION

System Settings

RID (Relay identification) = _____

TID (Terminal identification) = _____

MVA (Maximum transformer rating) = _____

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Current transformer connection	W1CT = _____	W2CT = _____	W3CT = _____	W4CT = _____
Current transformer ratio	CTR1 = _____	CTR2 = _____	CTR3 = _____	CTR4 = _____
Current transformer polarity	W1CT = _____	W2CT = _____	W3CT = _____	W4CT = _____
Nominal line-to-line voltage (kV)	VWDG1 = _____	VWDG2 = _____	VWDG3 = _____	VWDG4 = _____
Tap calculation	TAP1 = _____	TAP2 = _____	TAP3 = _____	TAP4 = _____

Differential Settings

O87P = _____ SLP1 = _____ SLP2 = _____ IRS1 = _____ US7P = _____

Metered Load (Data taken from substation panel meters, not the SEL-387 Relay)

± Readings from meters	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Megawatts	MW1 = _____	MW2 = _____	MW3 = _____	MW4 = _____
Megavars	MVAR1 = _____	MVAR2 = _____	MVAR3 = _____	MVAR4 = _____
MVA calculation				
$MVA_n = \sqrt{MW_n^2 + MVAR_n^2}$	MVA1 = _____	MVA2 = _____	MVA3 = _____	MVA4 = _____

Calculated Relay Load

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Primary Amperes calculation				
$I_{pri} = \frac{MVA_n \cdot 1000}{\sqrt{3} \cdot VWDG_n}$	I1pri = _____	I2pri = _____	I3pri = _____	I4pri = _____
Secondary Amperes calculation				
$WnCT = Y, I_{sec} = \frac{I_{pri}}{CTR_n}$	I1sec = _____	I2sec = _____	I3sec = _____	I4sec = _____
$WnCT = D, I_{sec} = \frac{I_{pri} \cdot \sqrt{3}}{CTR_n}$				

COMMISSIONING TEST WORKSHEET

SEL-387 Relay

Page 2 of 2

CONNECTION CHECK

Differential Connection (issue **MET DIF<ENTER>** to serial port or front panel)

Note: System load conditions should be higher than 0.1 A secondary. 0.5 A secondary is recommended for the best results.

Operate Current: IOP1 = _____ IOP2 = _____ IOP3 = _____

Restraint Current: IRT1 = _____ IRT2 = _____ IRT3 = _____

Mismatch Calculation:


$MMn = IOPn / IRTn$ MM1 = _____ MM2 = _____ MM3 = _____

Check individual current magnitudes, phase angles, and operate and restraint currents in an event report if mismatch is not less than 0.10

MAGNITUDE, ANGLE, AND PHASE ROTATION CHECK

(issue **MET SEC<ENTER>** to the serial port or front panel)

	Winding 1	Winding 2	Winding 3	Winding 4
A-Phase Secondary Amperes:	IAW1 = _____	IAW2 = _____	IAW3 = _____	IAW4 = _____
A-Phase Angle:	_____	_____	_____	_____
B-Phase Secondary Amperes:	IBW1 = _____	IBW2 = _____	IBW3 = _____	IBW4 = _____
B-Phase Angle:	_____	_____	_____	_____
C-Phase Secondary Amperes:	ICW1 = _____	ICW2 = _____	ICW3 = _____	ICW4 = _____
C-Phase Angle:	_____	_____	_____	_____



1. Calculated relay amperes match MET SEC amperes?
2. Phase rotation is as expected for each winding?
3. Do angular relationships among windings correspond to expected results? (Remember that secondary current values for load current flowing out of a winding will be 180° out of phase with the reference phase position for that winding. The reason is that ct polarity marks normally face away from the transformer on all windings.)

COMMISSIONING TEST WORKSHEET

SEL-387 Relay

Page 1 of 2

SYSTEM INFORMATION

System Settings

RID (Relay identification) = _____

TID (Terminal identification) = _____

MVA (Maximum transformer rating) = _____

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Current transformer connection:	W1CT = _____	W2CT = _____	W3CT = _____	W4CT = _____
Current transformer ratio:	CTR1 = _____	CTR2 = _____	CTR3 = _____	CTR4 = _____
Current transformer polarity:	W1CTP = _____	W2CTP = _____	W3CTP = _____	W4CTP = _____
Nominal line to line voltage (kV):	VWDG1 = _____	VWDG2 = _____	VWDG3 = _____	VWDG4 = _____
Tap calculation:	TAP1 = _____	TAP2 = _____	TAP3 = _____	TAP4 = _____

Differential Settings

O87P = _____ SLP1 = _____ SLP2 = _____ IRS1 = _____ U87P = _____

Metered Load (Data taken from substation panel meters, not the SEL-387 Relay)

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
± Readings from meters				
Megawatts:	MW1 = _____	MW2 = _____	MW3 = _____	MW4 = _____
Megavars:	MVAR1 = _____	MVAR2 = _____	MVAR3 = _____	MVAR4 = _____
MVA calculation				
$MVA_n = \sqrt{MW_n^2 + MVAR_n^2}$	MVA1 = _____	MVA2 = _____	MVA3 = _____	MVA4 = _____

Calculated Relay Load

	<u>Winding 1</u>	<u>Winding 2</u>	<u>Winding 3</u>	<u>Winding 4</u>
Primary Amperes calculation:				
$I_{pri} = \frac{MVA_n \cdot 1000}{\sqrt{3} \cdot VWDG_n}$	I1pri = _____	I2pri = _____	I3pri = _____	I4pri = _____
Secondary Amperes calculation:				
$I_{sec} = \frac{I_{pri}}{CTR_n}$	I1sec = _____	I2sec = _____	I3sec = _____	I4sec = _____
$I_{sec} = \frac{I_{pri} \cdot \sqrt{3}}{CTR_n}$				

COMMISSIONING TEST WORKSHEET

SEL-387 Relay

Page 2 of 2

CONNECTION CHECK

Differential Connection (issue MET DIF<ENTER> to serial port or front panel)

Note: System load conditions should be higher than 0.1 A secondary. 0.5 A secondary is recommended for the best results.

Operate Current: IOP1 = _____ IOP2 = _____ IOP3 = _____

Restraint Current: IRT1 = _____ IRT2 = _____ IRT3 = _____

Mismatch Calculation:


$MMn = IOPn / IRTn$ MM1 = _____ MM2 = _____ MM3 = _____

Check individual current magnitudes, phase angles, and operate and restraint currents in an event report if mismatch is not less than 0.10

MAGNITUDE, ANGLE, AND PHASE ROTATION CHECK

(issue MET SEC<ENTER> to the serial port or front panel)

	Winding 1	Winding 2	Winding 3	Winding 4
A-Phase Secondary Amperes	IAW1 = _____	IAW2 = _____	IAW3 = _____	IAW4 = _____
A-Phase Angle	_____	_____	_____	_____
B-Phase Secondary Amperes	IBW1 = _____	IBW2 = _____	IBW3 = _____	IBW4 = _____
B-Phase Angle	_____	_____	_____	_____
C-Phase Secondary Amperes	ICW1 = _____	ICW2 = _____	ICW3 = _____	ICW4 = _____
C-Phase Angle	_____	_____	_____	_____



1. Calculated relay amperes match MET SEC amperes?
2. Phase rotation is as expected for each winding?
3. Do angular relationships among windings correspond to expected results? (Remember that secondary current values for load current flowing out of a winding will be 180° out of phase with the reference phase position for that winding. The reason is that ct polarity marks normally face away from the transformer on all windings.)